



901 King Street West

901 King Street West
Toronto, ON, M5V 3H5



WiredScore
GOLD



Available ISPs

| Carrier | Cable Type |
|----------------|-----------------------|
| Aptum (Cogeco) | Fibre to the building |
| Beanfield | Fibre to the building |
| Bell | Fibre to the building |
| Bell Fibe | Fibre to the building |
| Rogers | Fibre to the building |
| Rogers | Coaxial |
| Telus | Fibre to the building |
| Zayo | Fibre to the building |

Key Features of Connectivity

- There is a choice of 7 service providers offering high speed connectivity (fibre or fixed wireless)
- Free Wi-Fi is provided in common and amenity areas to enhance access to connectivity within the building
- Multiple communications points of entry into the building provide tenants with the ability to utilize diverse connections
- The communications Points of Entries have available capacity for additional service providers to enter the building
- Service provider equipment is located in a secure and dedicated room to protect against potential damage
- The telco room has available capacity for the installation of additional service provider equipment
- Multiple communications risers allow physical diversity to protect against potential disruption
- There is available capacity within the risers for new service providers to supply service to tenants

WiredScore Certification Factsheet Explainer

Connectivity

| | |
|-------------------------|---|
| Fibre | The most technologically advanced cabling used in buildings. Fibre provides dedicated high speed connections with equal download and upload speeds. This is a symmetric solution with upload & download speeds up to 10,000Mbps. |
| Fixed wireless | Rooftop based antenna networks are used for both primary and secondary forms of connectivity. This is a top choice for secondary connections because it doesn't rely on the existing cabling into a building. This is a symmetric solution with upload and download speeds up to 2,000Mbps. |
| Coaxial cable | Used in most cable provider networks to provide the link between the external fibre network and the installation. This is an asymmetric solution with upload speeds up to 50Mbps and download speeds up to 1,000Mbps. |
| Wi-Fi | Providing free Wi-Fi in common and amenity areas enables tenants and their guests to remain connected throughout the building and can also be used for Wi-Fi calling. |
| Full Fibre distribution | Having multiple fibre access points pre-run throughout the building enables quicker installation of connections to tenants. |
| Type 2 Providers | Carriers that do not own their own cabling entering the building, and service tenants "piggy backing" on another provider's network. |

Infrastructure

| | |
|----------------------|--|
| Point of entry | "POEs" are the telco cable entry points into the building. Having multiple POEs from different locations or sides of the building creates a physical separation; therefore, if the connectivity on one side of the building is disrupted, connectivity from the other side can still be functional. |
| Telco room | A location in the building where provider's equipment is installed. Separation of telco equipment from that of other utilities, such as electricity, gas or water reduces the personnel able to access the telco equipment servicing tenants. This mitigates the risk of accidental disruption to the telco equipment that is servicing tenants. |
| Communication risers | A pathway that runs vertically from the bottom to the top of the building. Access to communication risers should be via secure access points on each floor. Risers in diverse locations, with capacity for future installations, ensure that providers can deliver reliable and resilient services to all tenants in the building. |
| Back-up generators | Providing a connection from the building's back-up generator to the telco room enables continuation of tenant connectivity through power outages. |
| Capacity | The ability to support new telecommunications cabling and equipment utilizing the existing building infrastructure. Having spare capacity prevents costly installation fees when providers are delivering service. |

Readiness

| | |
|----------------------------------|--|
| Access Agreements with providers | These agreements lay out ownership rules and regulations for operating as a service provider in the building. These documents ensure that current service providers have permission to sell and deliver services to tenants. |
| Standard Telecom Agreement | A standard telecommunications agreement template describes the landlord's rules for installing, maintaining and removing telco equipment. Existence of these proactively developed terms & conditions helps ensure there is a streamlined process in place to allow new providers to supply service to the building. This can reduce delays for tenants signing up for internet service. |
| Building Install and Access Pack | A package of outlined access procedures, routes and locations for telco equipment/cabling, and specifications for installations. This package enables tenants and providers to gain visibility on how any new or current installation should be implemented. |